BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/03/2018-19 Dated: 1[illegible]-12-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 05

Name of Work: Emergency works in ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. R Ranganath	
				Rate	Rate in Words
1	Excavation and removal of silt or silt mixed with sand in slussy condition from canal bed including disposing off the same in spoil bankor on the canal embankment in layers as directed etc., complete withinitial lead upto 50 m and all lifts. MISR 2014-15 Page No 131 item No 51	cum	972.00	129.36	Rupees One Hundred Twenty Nine and Paise Thirty Six Only
2	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no143, PWD SR 2018-19)	cum	27.00	121.26	Rupees One Hundred Twenty One and Paise Twenty Six Only
3	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 136 (SR 2018-19)	cum	999.00	77.05	Rupees Seventy Seven and Paise Five Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. R Ranganath	
				Rate	Rate in Words
4	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)/ PWD SR 2018-19	Cum	12.45	4759.15	Rupees Four Thousand Seven Hundred Fifty Nine and Paise Fifteen Only
5	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 271 Ite mo 37.59.2 SR 2018-19	Cum	28.80	6221.78	Rupees Six Thousand Two Hundred Twenty One and Paise Seventy Eight Only
6	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Tonne	1.97	66197.08	Rupees Sixty Six Thousand One Hundred Ninety Seven and Paise Eight Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. R Ranganath	
				Rate	Rate in Words
	RCC Precast covering slab for drain (10cm thick)	sqm	45.00	1848.00	Rupees One Thousand Eight Hundred Forty Eight Only
8	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge-	sqm	21.60	4497.68	Rupees Four Thousand Four Hundred Ninety Seven and Paise Sixty Eight Only
9	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete. Page No. 27/ Item No. 5.29/ PWD SR 2018-19	Nos	444.00	419.76	Rupees Four Hundred Nineteen and Paise Seventy Six Only
10	Engaging on Hire Basis JCB including Driver/operator with fuel etc complete (SR 2018-19) Page No XLVIII code 1031) Sl No 23	Day	4.00	5011.60	Rupees Five Thousand Eleven and Paise Sixty Only
11	Engaging on Hire basis of Tractor 50 HP for Conveying of excavated and removal of Stuff from work spot (SR 2018-19) Page No XLVIII code 1024) Sl No 23	Day	40.00	2210.56	Rupees Two Thousand Two Hundred Ten and Paise Fifty Six Only
12	Labour charges to Unskilled Mazdoor Heavy (Page no .LIV)SR 2018-18 sl No 5	Day	320.00	392.66	Rupees Three Hundred Ninety Two and Paise Sixty Six Only

Signature of the Contractor

Executive Engineer

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Bruhat Bangalore
ANGALORE